

## Residential drop off facility Alkmaar



**Customer:** HVC

Mr J. Ligthart

Jadestraat 1, 1812 RD

Alkmaar, Netherlands

Po Box 9199, 1800 GD Alkmaar, Netherlands

Website: [www.hvcgroep.nl](http://www.hvcgroep.nl)

Email: [j.ligthart@hvcgroep.nl](mailto:j.ligthart@hvcgroep.nl)

Tel: +31 725411311

**Site Location:**

Jadestraat 1, 1812 RD

Alkmaar, Netherlands

Contact details Modulo-béton: Ron van Ommeren, Modulo Béton, Cell +31 652386780, work +31 355885454 , [rvommeren@modulo-beton.nl](mailto:rvommeren@modulo-beton.nl) , Lange Brinkweg 81 , 3764 AB Soest, The Netherlands

**Construction:** 2012

**Projectvalue:** € 999,999mio

**Site surface:** 4,160 m<sup>2</sup>

**Number of blocks:** 82

**Space underneath the deck:** 700 m<sup>2</sup>

**Capacity:** 14 bins @ 40 m<sup>3</sup> Modulo system, 8 Conventionalpart of the system

**Project details:** Alkmaar desired a multifunctional flexible solution on a very small surface area.

The site has heattraced ramps and facilitates offices, storage, reuse and HHW underneath the deck.

The site is in compliance with all European and Dutch Regulations (Guidelines for Environmental Protection Measures and Chemical Waste Storage, National and International Fire Codes). It has all fire safety features, including 3 hours fire rated walls, fire rated self closing doors, spill containment with self-contained sumps, chemical resistant removable gratings, certified electrical, electrical centre connections, outlets, emergency eye/face wash station, lockable doors, emergency lights, exterior lightning, insulation, heating and temperature control, ventilation, shelves, access into each compartment, warranty

**Additional info:** 94,270 residents, 44,680 households

